



The Certification Mark for Onsite
Sustainable Energy Technologies

Microgeneration Installation Standard: MIS 3007-2

REQUIREMENTS FOR CONTRACTORS UNDERTAKING THE DESIGN, SUPPLY, INSTALLATION, SET TO WORK, COMMISSIONING AND HANDOVER OF A DOMESTIC HOT WATER SYSTEM CONTAINING AN ELECTRICITY LED MICRO-COGENERATION PACKAGE

Issue 1.0

This document was prepared by the Microgeneration Certification Scheme Working Group 9 'Micro-CHP systems'.

This document has been approved by the Steering Group of the Microgeneration Certification Scheme.

REVISION OF MICROGENERATION INSTALLATION STANDARDS

Installation Standards will be revised by issue of revised editions or amendments. Details will be posted on the website at www.microgenerationcertification.org

Technical or other changes which affect the requirements for the approval or certification of the product or service will result in a new issue. Minor or administrative changes (e.g. corrections of spelling and typographical errors, changes to address and copyright details, the addition of notes for clarification etc.) may be made as amendments.

The issue number will be given in decimal format with the integer part giving the issue number and the fractional part giving the number of amendments (e.g. Issue 3.2 indicates that the document is at Issue 3 with 2 amendments).

Users of this standard should ensure that they possess the latest issue and all amendments.

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 2 of 18

TABLE OF CONTENTS

FOREWORD.....	4
1. SCOPE.....	5
2. DEFINITIONS	5
3. REQUIREMENTS FOR THE CERTIFICATED CONTRACTOR	7
3.1 Capability	7
3.2 Quality management system	7
3.3 Sub contracting	7
3.4 Consumer code of practice	8
4. DESIGN AND INSTALLATION, SET TO WORK, COMMISSIONING, HANDOVER AND EQUIPMENT REQUIREMENTS.....	9
4.1 Regulations.....	9
4.2 Design and installation.....	9
4.3 Set to Work & Commissioning	11
4.4 Handover	11
4.5 Equipment.....	11
5. COMPETENCE OF STAFF	12
6. REGIONAL OFFICES	13
7. PUBLICATIONS REFERRED TO	13
APPENDIX A: QUALIFICATIONS OF STAFF	16
APPENDIX B: Environmental performance	17
AMENDMENTS ISSUED SINCE PUBLICATION	18

FOREWORD

This document identifies the evaluation and assessment practices undertaken by certification bodies of the Microgeneration Certification Scheme (MCS) for the purposes of approval and listing of contractors undertaking the design, supply, installation, set to work, commissioning and handover of a domestic hot water system containing a micro-cogeneration package. The listing and approval is based on evidence acceptable to the certification body:

- that the contractor has staff, processes and systems in place to ensure that the system or service delivered will meet the requirements of this standard

And on:

- periodic audits of the Contractor including testing as appropriate; and
- compliance with the contract for the MCS listing and approval including agreement to rectify faults as appropriate

This standard shall be used in conjunction with document MCS 001 (see Ref. [7.1]).

NOTES:-

This Installation Standard makes use of the terms ‘must’, ‘shall’ and ‘should’ when prescribing certain requirements and procedures. In the context of this document:

- *The term ‘must’ identifies a requirement by law at the time of publication*
- *The term ‘shall’ prescribes a requirement or procedure that is intended to be complied with in full and without deviation*
- *The term ‘should’ prescribes a requirement or procedure that is intended to be complied with unless reasonable justification can be given*

Compliance with this Installation Standard does not of itself confer immunity from legal obligations.

The Steering Group welcomes comments of a technical or editorial nature and these should be addressed to “the Secretary” at mcs@gemserv.com

Listed products and services appear at www.microgenerationcertification.org.

The objective of Government’s Micro-generation strategy is to create conditions under which Micro-generation becomes a realistic alternative or supplementary energy generation source for the householder, for the community and for small businesses.

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 4 of 18

1. SCOPE

This standard specifies the requirements of the Microgeneration Certification Scheme (MCS) for the approval and listing of Contractors undertaking the design, supply, installation, set to work, commissioning and handover of a domestic hot water system containing a micro-cogeneration package.

The micro-cogeneration packages covered by this standard are those described in the MCS Product Certification Scheme requirements MCS 015 (see Ref. [7.2])

Note: Currently this Standard refers to electricity led micro-CHP that use the heat by product for domestic hot water generation only. This will be extended to cover domestic heating as testing methodologies are developed.

2. DEFINITIONS

Commissioning	The activities to ensure that the installed system operates within the boundaries and conditions of the design and the product manufacturers' claims.
Contract	A written undertaking for the design, supply, installation, set to work, commissioning and handover of a domestic hot water system containing a micro-cogeneration package.
Contractor	An individual, body corporate or body incorporate, applying for or holding certification for the services detailed in the Scope, Clause 1, above.
Design	The formulation of a written plan including a specific list of products and fixings to form a completed domestic hot water system containing a defined electricity-led micro-cogeneration unit or package installation in a dwelling.
Handover	The point in a Contract where commissioning and certification of the system have been satisfactorily completed to the Contract specification so enabling the installation to be formally handed over to the client.
Installation	The activities associated with placement and fixing of a domestic hot water system containing an electricity-led micro-cogeneration

	package.
Set to work	The activities necessary to make the domestic hot water system containing an electricity-led micro-cogeneration unit or package system function as a completed system.
Sub-contract	A written contract between a certificated contractor and another Firm for supply of products and services in connection with the fulfilment of a Contract.

3. REQUIREMENTS FOR THE CERTIFICATED CONTRACTOR

3.1 CAPABILITY

The Contractor shall have the capability to undertake the design, supply, installation, set to work, commissioning and handover of the domestic hot water system containing the micro-cogeneration unit or package.

Where Contractors do not engage in the design or supply of such systems, but work solely as an installer for a client who has already commissioned a system design; then the Contractor shall be competent to review and verify that the design will meet the design requirements set out in this scheme document and this should be recorded.

3.2 QUALITY MANAGEMENT SYSTEM

Contractors shall operate a satisfactory quality management system which meets the additional requirements set out in the scheme document MCS 001

3.3 SUB CONTRACTING

In installations for private customers, any work within the scope of the scheme not undertaken by employees of the Contractor shall be managed through a formal subcontract agreement between the two parties in accordance with the policies and procedures employed by the certificated Contractor. These procedures shall ensure that the subcontractor undertakes the work in accordance with the requirements of this standard.

In other situations (for example new build, or for commercial customers), it is permissible for the physical installation, setting to work and commissioning to be undertaken by others (i.e. not sub-contracted to the Contractor) provided that:

3.3.1 A contract between the Contractor and the commercial client details obligations on the client to include that evidence of skills and training of those employed by the client to do elements of work not undertaken by the Contractor are to be made available to the Contractor to ensure that the competence requirements of this standard are met and that access to the site for training and supervision in accordance with the following sections is agreed in advance.

3.3.2 The certificated Contractor provides additional product-specific training for those undertaking the work not undertaken by the certificated Contractor.

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 7 of 18

3.3.3 The certificated Contractor assesses a sample number of installations under the contract which is not less than the square root of the number of installations rounded up to the nearest whole number (e.g. a new build site of 50 installations then a minimum of 8 are assessed).

3.3.4 The certificated Contractor assumes responsibility at handover that the installation is in full compliance with the standard.

3.4 CONSUMER CODE OF PRACTICE

The Contractor shall be a member of and shall comply with, a code of practice (consumer code), which is relevant to the scope of their business in the Microgeneration sector and which is approved by the Office of Fair Trading (OFT), (e.g. REAL Assurance Scheme Consumer Code {see Ref. [7.4]}).

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 8 of 18

4. DESIGN AND INSTALLATION, SET TO WORK, COMMISSIONING, HANDOVER AND EQUIPMENT REQUIREMENTS

4.1 REGULATIONS

All applicable regulations and directives must be met in full. It should be noted that regulations that must be applied may be different in England and Wales, Scotland and Northern Ireland. Some guidance on applicable regulations is given in the guidance document MCS 002 (see Ref. [7.5]). This guidance is not necessarily exhaustive and may change from time to time. Certificated contractors shall ensure they have a system to identify all applicable regulations and changes to them.

All work, and working practices, must be in compliance with all relevant health and safety regulations and a risk assessment shall be conducted before any work on site is commenced.

4.2 DESIGN AND INSTALLATION

The areas of competence relevant to the design and installation of electricity-led micro-cogeneration package systems in dwellings are included in Clause 5. The following principles shall be met when selecting, designing, specifying and installing such systems.

4.2.1 The environmental performance of the micro-cogeneration unit or package shall be equal or better than would be achieved by a boiler using the same fuel and grid supplied electricity. This shall be determined by the method set out in Annex 1 of MCS015.

4.2.2 The design of the installation shall ensure that it complies with the following fundamental assumptions:

- a) The micro-cogeneration package is a standalone electricity led product system for the dwelling.
- b) Water heating service throughout the year is the sole thermal function;
- c) The package is controlled by electric demand (i.e. it is “electricity-led”);
- d) Heat is never wasted; and

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 9 of 18

e) Electricity is never wasted, and any that is not used in the dwelling is always exported to the grid.

4.2.3 The design of the micro-cogeneration unit or package system shall be in compliance with the micro-cogeneration unit or package manufacturer's specification and shall be clearly documented so that such compliance may be demonstrated.

4.2.4 The micro-cogeneration unit or package system shall be installed such that all the manufacturer's instructions are followed, including noise considerations (referring to the results of the noise report obtained from fulfilling MCS 015 – Section 8 Technical Documentation).

4.2.5 The micro-cogeneration unit or package shall be connected to the domestic electrical installation (in parallel with the mains supply) by following the appropriate guidance contained in the Guide prepared by the Electrical Safety Council "Connecting a microgeneration system to a domestic or similar electrical installation (in parallel with the mains supply)" (see Ref. [7.9]).

4.2.6 a) For new build the Contractor shall provide evidence of consultation and compliance with the requirements of the designers and installers of the building's energy system regarding specification and performance to ensure the correct and efficient operation of the system as a whole. This shall cover the selection of a micro-cogeneration package of appropriate output for the DHW demands of the building,.

b) When replacing an existing hot water system the Contractor shall provide evidence that the micro-cogeneration unit or package and associated components selected is of appropriate output for the building, and that the design of the heat distribution systems and controls is compatible with efficient operation of the package and the system as a whole.

4.2.7 The Contractor shall ensure the customer is aware from the outset that metering will be required if the customer wishes to access certain financial incentive schemes. The contractor will ensure the customer has the opportunity to take account of this when awarding the contract.

Note: for guidance on metering requirements please follow MCS Metering Guidance v1.0, available from the Standards section of <http://www.microgenerationcertification.org/>

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 10 of 18

4.3 SET TO WORK & COMMISSIONING

The micro-cogeneration package system shall be commissioned according to the manufacturer's requirements.

4.4 HANDOVER

Contractors shall provide the client with a comprehensive document pack and that pack should contain at least:

- The system maintenance requirements and the maintenance services available;
- The micro-cogeneration or package manufacturer's User and Installation and Service Instructions;
- A certificate signed by the contractor containing at least the following:
 - a statement confirming that the micro-cogeneration package system installation meets the requirements of this standard;
 - Client name and address;
 - Site address (if different);
 - Contractors name, address etc.;
 - List of key components installed; and
 - A description of the system performance including those parameters applicable to the specific installation listed in 4.2.2.
 - A certificate obtained from the MCS Installation Database, showing that the installation has been registered with the scheme (to be provided within 10 working days of the commissioning date).

Note: all MCS Installations must be notified to the MCS Licensee through the MCS Installation Database, where a certificate will be generated and sent to the customer. There is a £5 per installation fee levied on installers for each installation added to the database.

4.5 EQUIPMENT

When making installations in accordance with this standard the micro-cogeneration package used in installations shall be listed under the MCS (<http://www.microgenerationcertification.org>).

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 11 of 18

All micro-cogeneration packages that are installed within the European Union must be CE marked in compliance with the relevant European Directives. Examples are listed in MCS 002.

5. COMPETENCE OF STAFF

All personnel employed by, or sub-contracted to, the Contractor shall be able to demonstrate that they are trained and competent in the disciplines and skills, appropriate to the activities required for their role, in accordance with this standard.

Complete records of training and competence skills of personnel shall be maintained by the certificated contractor, in particular:

- Design staff, carrying out full conceptual design, shall be able to demonstrate a thorough knowledge of the technologies involved and the interaction of associated technologies;
- All personnel engaged in the actual installation are expected to have technical knowledge and installation skills, to install components and equipment within the designed system, in accordance with all appropriate codes of practice, manufacturer's specifications and regulations; and
- All personnel engaged in the final inspection, commissioning, or repair shall have a comprehensive technical knowledge of the products, interfacing services and structures to complete the specified processes.

Examples of qualifications that may be suitable for satisfying the training requirements are listed in Appendix A.

Note: Due to the current development of the Sector Skills Agreement and the review in progress of the National Occupational Standards for this technology, the indicated suggested scope in the Appendix "A", may change.

For personnel employed in the installation of micro-cogeneration packages assessments of training and competence will cover the following underpinning knowledge areas:

- Health and Safety knowledge and awareness including risk assessments;

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 12 of 18

- Energy conservation including the requirements of the Building Regulations Schedule 1 Part L for new and existing buildings;
- Assessment of the suitability of an electricity-led micro-cogeneration package system for the building and the efficient operation of its domestic hot water system;
- After-sales service and warranty;
- Awareness of different electricity tariffs;
- Fault diagnosis;
- Performance data to be supplied;
- Commissioning;
- Environmental considerations – e.g. minimising risk of nuisance from noise and combustion products;
- How electricity-led micro-cogeneration packages work – principles and components;
- Electrical connections – e.g. Competent Persons Scheme *Electrical Safety in dwellings* (see Ref. [7.10]);
- Plumbing connections – e.g. Competent Persons Scheme *Heating and Hot Water Service Systems (Dwellings)* see Ref. [7.10]); and

6. REGIONAL OFFICES

Where the Contractor wishes to design, install and commission under the Certification Scheme in regional offices, then these offices shall meet the requirements of this standard to be eligible for Certification.

7. PUBLICATIONS REFERRED TO

In the following list reference to undated publications implies the latest edition and amendments:

[7.1] MCS 001- Microgeneration Certification Scheme – Installer certification scheme document - Available from www.microgenerationcertification.org

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 13 of 18

[7.2] MCS 015

MCS 015 – Microgeneration Certification Scheme - Product certification scheme requirements *Electricity-led micro-cogeneration packages in dwellings* - Available from www.microgenerationcertification.org

[7.3] PAS 67: 2008 (updated July 2010) – Publicly Available Specification 67 - Laboratory tests to determine the heating and electrical performance of heat-led and electricity-led micro-cogeneration packages primarily intended for heating dwellings – Available from BSI Customer Services Tel: +44 (0)20 8996 9001

[7.4] REAL Assurance Scheme Consumer Code – see <http://www.realassurance.org.uk/about-the-code>

[7.5] MCS 002 – Guidance on regulations and directives for Microgeneration installations - Available from www.microgenerationcertification.org

[7.6] The Boiler Efficiency Database – see www.sedbuk.com

[7.7] *Method to evaluate the annual energy performance of micro-cogeneration heating systems in dwellings, 9 October 2008*. Prepared for Sustainable Energy Policy Division, Defra, by John Hayton and Bruce Young, BRE. Available from: <http://projects.bre.co.uk/SAP2005/supporting-technical-documents.html>

[7.8] SAP - *The Government's Standard Assessment Procedure for Energy Rating of Dwellings* – 2005 Edition – see <http://projects.bre.co.uk/sap2005/pdf/SAP2005.pdf>

[7.9] “*Connecting a microgeneration system to a domestic or similar electrical installation (in parallel with the mains supply)* – Best Practice Guide produced by the Electrical Safety Council – see http://rexel.tamba.co.uk/client_files/File/NE/BestPracticeGuide3.pdf

[7.10] Competent Persons Scheme *Electrical Safety in dwellings* AND Competent Persons Scheme *Heating and Hot Water Service Systems (Dwellings)* – see

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 14 of 18

<http://www.communities.gov.uk/planningandbuilding/buildingregulations/competentpersonsschemes/existingcompetentperson/>

[7.11] IGE/UP/3 Edition 2 *Gas fuelled spark ignition and dual fuel engines* – see <http://www.igem.org.uk/technical/publications.asp?mci=4>

[7.12] ACS Module CGFE1 (Commercial Gas Fired Engines)

[7.13] *Domestic Heating Design Guide* published by CIBSE

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 15 of 18

APPENDIX A: QUALIFICATIONS OF STAFF

The following qualifications may be suitable to satisfy the training requirements detailed under Clause 5:

- Accreditation from a relevant training course – relevance of the course would require independent verification.
- Membership of a relevant Competent Person Scheme – relevance of the Competent Person Scheme would require independent verification.
- Micro-cogeneration package manufacturer's product training – Would be product specific and require independent verification.
- Experience gained through a mentoring process – would require independent verification.
- Demonstrable track record of successful installation – would require independent verification.

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 16 of 18

APPENDIX B: ENVIRONMENTAL PERFORMANCE

B.1 Standard of comparison

B.1.1 The environmental performance of the micro-cogeneration package shall be evaluated and compared with that of a boiler using the same fuel and grid supplied electricity.

B.1.2 For a micro-cogeneration package fuelled by natural gas, LPG, or oil, the standard for comparison shall be a boiler using the same fuel with a SEDBUK efficiency greater than or equal to SEDBUK 2005 – 90%/SEDBUK 2009 – 88%, representative of good quality products readily available in the market.

B.1.3 For a micro-cogeneration package not covered by B.1.2, the standard for comparison shall be a boiler using the same fuel and compliant with building regulations in respect of energy performance.

B.1.4 Performance shall be established in accordance with the methodology described in Annex D of PAS67. The carbon emissions value (C) shall be less than that of the reference boiler.

B.1.5 When communicated to the client, the estimate of performance shall be accompanied by the following disclaimer:

'The performance of Micro-cogeneration systems is difficult to predict with certainty due to the variability of customer expectations and usage and the subsequent effect on both heat demand and electricity supply and demand. This estimate is based upon the best available information but is given as guidance only and should not be considered as a guarantee.'

Issue: 1.0	MICROGENERATION INSTALLATION	MIS: 3007-2
Date: 16/11/2010	STANDARD	Page 17 of 18

AMENDMENTS ISSUED SINCE PUBLICATION

Document Number:	Amendment Details:	Date:
1.0	First Issue	16/11/10